

1. ALL FEDERAL, STATE, AND LOCAL CODES SHALL BE STRICTLY OBSERVED DURING THE CONSTRUCTION OF THE PROJECT. BRING ANY DISCREPANCIES BETWEEN THE CONSTRUCTION DOCUMENTS AND THE APPLICABLE CODES TO THE ATTENTION OF THE DESIGN CONSULTANT.
2. CONTRACTOR SHALL OBTAIN ALL APPLICABLE BUILDING PERMITS FROM THE VILLAGE OF LAKEWOOD AND CHAUTAUQUA COUNTY.
3. CONTRACTOR SHALL CONTACT DIG SAFELY NEW YORK (811) TO IDENTIFY AND PROTECT ALL UTILITY LINES.
4. CONTRACTOR SHALL NOTIFY PROPERTY OWNER(S) PRIOR TO STARTING WORK.
5. DESIGN CONSULTANT SHALL NOT BE RESPONSIBLE FOR SAFETY, CONSTRUCTION PROCEDURES, TECHNIQUES, OR THE FAILURE OF THE CONTRACTOR TO CARRY OUT THE WORK IN ACCORDANCE WITH THE DRAWINGS, SPECIFICATIONS, OR THE REQUIRED CODES.
6. CONTRACTOR SHALL VERIFY ALL DIMENSIONS, MATERIAL ESTIMATES, ACCESS ROUTES, AND SITE CONDITIONS PRIOR TO STARTING WORK.
7. CONTRACTOR SHALL BRING ERRORS AND OMISSIONS WHICH MAY OCCUR IN THE CONTRACT DOCUMENTS TO THE ATTENTION OF THE DESIGN CONSULTANT BEFORE PROCEEDING WITH THE WORK.
8. CONTRACTOR SHALL IMMEDIATELY NOTIFY OWNER AND DESIGN CONSULTANT IF ABNORMAL CONDITIONS ARE ENCOUNTERED DURING CONSTRUCTION, OR IF DESIGN CHANGES ARE ANTICIPATED, INCLUDING SPECIFIED MATERIAL.
9. CONTRACTOR SHALL MAINTAIN A CLEAN WORK AREA FREE OF ALL TRASH AND DEBRIS AND SHALL PROTECT ALL ADJACENT WORK AREAS.
10. CONTRACTOR SHALL FAMILIARIZE THEMSELF AND ALL SUBCONTRACTORS WITH THE DRAWINGS, SPECIFICATIONS, AND SPDS PERMIT FOR THE PROJECT.

1. CONTRACTOR WILL MAKE EVERY EFFORT TO PERFORM EARTH DISTURBING ACTIVITIES DURING DRY WEATHER CONDITIONS.
2. CONTRACTOR WILL KEEP ALL POLLUTANTS AND SEDIMENT FROM LEAVING THE SITE.
3. CONTRACTOR WILL INSTALL TEMPORARY EGS CONTROLS SUCH AS STRAW BALES, SILT FENCE, FIBER ROLLS, OR OTHER EGS CONTROLS AT CRITICAL AREAS DURING CONSTRUCTION TO CONTAIN SEDIMENT WITHIN THE WORK AREA. CONTRACTOR WILL REMOVE TEMPORARY EGS CONTROLS AFTER SITE STABILIZATION IS COMPLETE. CONTRACTOR WILL INSTALL ALL EGS CONTROLS PER NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL.
4. CONTRACTOR TO INSTALL EGS CONTROL AROUND THE PERIMETER OF THE EXISTING DI, SUCH AS STRAW BALES, FILTER SOCK, OR OTHER TEMPORARY EGS CONTROLS.
5. CONTRACTOR SHALL ALWAYS MAINTAIN GOOD HOUSEKEEPING PRACTICES AND A NEAT AND ORDERLY SITE.
6. CONTRACTOR WILL KEEP ALL CONSTRUCTION MATERIALS AND STOCKPILES CONTAINED ON-SITE AND AT LEAST 10' FROM CONCENTRATED STORMWATER FLOW PATHS. CONTRACTOR WILL INSTALL SILT FENCE OR OTHER PERIMETER EGS CONTROLS AS NECESSARY AROUND STOCKPILES.
7. CONTRACTOR WILL SEED AND MULCH BARE SOIL AREAS AND SOIL STOCKPILES EXISTING FOR MORE THAN 14 DAYS.
8. CONTRACTOR WILL PROMPTLY SEED AND MULCH ALL DISTURBED AREAS AFTER CONSTRUCTION. STABILIZATION WILL BE ACHIEVED WHEN THERE IS NO BARE SOIL AREAS AND A UNIFORM 80% EROSION RESISTANT PERENNIAL VEGETATIVE COVER.

New York State Route 394
a.k.a. East Fairmount Avenue
(Jamestown-Ashville S.H. No. 1380A)
5 Lane public roadway
Width Varies
Concrete Sidewalk

